PLAINTIFF'S EXHIBIT WRG-780

Chemical Waste Management, Inc.
Environmental Remedial Action Division
150 W 137th Street
Riverdale, Illinois 60627
[redacted]

RECEIVED NOV 5 1984

November 1, 1984

Emerson & Cuming
W.R. Grace
Dewey and Almy Chemical Div.
3450 Commercial Avenue
Northbrook, Illinois 60062

Attn: Robert L. Catardi

Dear Mr. Catardi,

Pursuant to my visit of your facility on October 26, Chemical Waste Management, Inc. (CWM), through its Environmental Remedial Action Division (ENRAC) is pleased to present the following proposal for removal, transportation and disposal of asbestos containing material on the three I-beams running through your plant.

Due to the hazardous nature of the asbestos fibers, removal operations must take place during non-working hours, limiting unnecessary exposure to any of your personnel. It is understood that as much stock as possible will be moved from under the beams and your forklift and basket will be available for ENRAC'S use.

ENRAC'S crew, wearing the appropriate respiratory protective and safety gear, will thoroughly wet the material to be removed with a water/glycol solution. This procedure minimizes the generation of airborne particulates during removal. Once wetted, ENRAC'S technicians will scrape the insulation off of the beams standing from ladders, scaffolding or the forklift basket. The insulation will be collected, using brooms, shovels and vacuuming equipment, and packaged in accordance with all the applicable regulations. Disposal will take place at Waste Management Inc.'s fully permitted CID-landfill in Calumet City, Illinois.

All the necessary personnel, safety equipment, tools, transportation and disposal would be provided for the sum of $ 7,392.00.

By utilizing the Waste Management family, you can take comfort in the fact that this project will be handled in an environmentally sound manner. ENRAC'S extensive experience in asbestos removal projects assures you of a safe and cost effective operation.

CWM appreciates this opportunity to serve you. If you have any questions or if I can be of further assistance, please contact me.

Sincerely,
CHEMICAL WASTE MANAGEMENT - ENRAC

Matthew G. Radek
Project Manager

cc: Michael J. McKinney
James R. McCarthy

MGR:ls

11/29/84

P.O. # 52666

Required Matt Radek call to make arrangements for removal & installing material.