

STEELITE, INC.

QUOTATION

1010 OHIO RIVER BLVD., PITTSBURGH, PA 15202 - AREA CODE 412-734-2600

TO: Southwestern Industrial
Contractors & Riggers, Inc.
P.O. Box 26976
El Paso, TX 79926

Attention: Mr. Hugh Wickes

QUOTATION NO. 8949-03 Date 7/16/79

Your Inquiry _____

Owner: Asarco

Project: Retrofit Project

Location: El Paso, TX

Gentlemen:

STEELITE, INC. PROPOSES TO FURNISH THE NECESSARY MATERIAL, DELIVERY OF MATERIAL, AND ENGINEERING DRAWINGS FOR THE ABOVE SUBJECT PROJECT AS SPECIFIED IN THE CONTRACT DOCUMENTS, PER THE ATTACHED PRICING DATA SHEET.

THIS PROPOSAL IS SUBJECT TO THE STATEMENT OF EXCEPTIONS, QUALIFICATIONS AND REQUIREMENTS, ALL OF WHICH ARE SET FORTH ON THE ATTACHED SHEETS WHICH ARE INCORPORATED HEREIN BY REFERENCE.

WE THANK YOU FOR THE OPPORTUNITY TO PROVIDE YOU WITH A QUOTATION FOR THIS WORK. IF THERE ARE ANY QUESTIONS, PLEASE LET US KNOW.

22GA - 412-224
2250
11
41
66

PLAINTIFF'S EXHIBIT

ASA-1247

TERMS: Net 30
ESTIMATED DELIVERY: SEE STATEMENT OF EXCEPTIONS,
QUALIFICATIONS AND REQUIREMENTS

Yours very truly,

Ed St. Martin

STEELITE, INC.

Ed St. Martin

Manager, Engineered Sales

cc: Joe Martin

This offer shall terminate 30 days from the date hereof. Steelite, Inc. objects to the inclusion of any different or additional terms in the acceptance of this offer and if buyer includes them in the acceptance of this offer, contract will result but only on Steelite, Inc.'s terms stated herein. Any shipment of goods shall be deemed made pursuant to Steelite, Inc.'s terms. Acceptance of any goods shall constitute buyer's acceptance of Steelite, Inc.'s terms.

This proposal is subject to all terms and conditions on the reverse side hereof, including limitation of warranties.

ORIGINAL

ASARCO ELP 0009549

Q# 8949-03

PRICING DATA SHEET

<u>Proposal</u>	<u>Wedge Roaster Building</u>	<u>Fines Crushing Plant</u>	<u>Coarse Crushing Plant</u>	<u>Conv. Housing</u>	<u>Total</u>
1) Base Bid (22 Ga. "CS" Tan Roof & Siding)	\$37,872	\$31,510	\$30,189	\$5,396	\$104,967
2) Alt. #1 ("CS" Tan, 20 Ga. Roof, 22 Ga. Siding)	\$39,012	\$32,293	\$31,267	\$5,615	\$108,187
3) Alt. #2 (22 Ga. "CS" Sand Roof & Siding)	\$38,437	\$31,991	\$30,635	\$5,470	\$106,533
4) Alt. #3 ("CS" Sand, 20 Ga. Roof, 22 Ga. Siding)	\$39,211	\$32,418	\$31,457	\$5,660	\$108,746

UNIT PRICE DATA SHEET

Q# 8949-03

- | | | |
|---|---|-------------|
| 1) | 20 Ga. Hi-Rib Panels with CS 400 Tan Finish | \$110.71/GS |
| 2) | 22 Ga. Hi-Rib Panels with CS 400 Tan Finish | \$ 96.13/GS |
| 3) | 20 Ga. Hi-Rib Panels with CS 400 Sand Finish | \$113.00/GS |
| 4) | 22 Ga. Hi-Rib Panels with CS 400 Sand Finish | \$ 98.19/GS |
| <p>NOTE: Item #3 & 4 prices based on materials being included with original order or as a minimum 40,000 lb. order.</p> | | |
| 5) | 20 Ga. CS 400 Tan or Sand Flats | \$ 1.18/S. |
| 6) | 22 Ga. CS 400 Tan or Sand Flats | \$ 1.03/S. |
| 7) | Fabrication of 12" wide, 3 break Flashing | \$ 0.75/L. |
| 8) | Hi-Rib Profile Neoprene Closures
(116 L.F./CTN.) | \$ 23.50/CT |
| 9) | Tremco #440 Lap Tape
(1,000 L.F./CTN.) | \$ 33.50/CT |
| 10) | Size #14, #305 S.S., Self Tapping Fasteners, Painted Heads | |
| | a) 3/4" long Type A | \$ 79.25/M |
| | b) 1" long Type B | \$ 93.99/M |
| 11) | Standard 8 oz., Hi-Rib Profile, Fiberglass Reinforced
Non Fire Retardent, Translucent Panels
(Stocked in 10', 12', 14' in Green or White Colors.) | \$ 80.00/G. |
| 12) | Freight Rates (Present Day)
(Based on 40,000 lb. load) | \$ 8.05/CW |

STATEMENT OF EXCEPTIONS, QUALIFICATIONS
AND REQUIREMENTS

I. Scheduling

A. Engineering Drawings: Engineering Drawings to be prepared in the following sequence with the indicated durations:

- 1) Wedge Roaster Building: 5 Days
- 2) Coarse Crushing Plant: 5 Days
- 3) Fines Crushing Plant: 5 Days
- 4) Conveyor Housing: 2 Days

This schedule is based upon one detailer preparing all of the drawings. Additional detailers can be added if necessary. One set of sepia and one set of prints to be provided per required submittal.

B. Fabrication and Delivery: Fabrication and shipment of material to begin as follows:

- 1) Based on Corrtan 400 Tan material: Approximately three to four weeks after receipt of approved erection drawings.
- 2) Based on Corrtan 400 Sand material: Delivery of coil coated material into roll forming plant approximately eight weeks after receipt of order. Fabrication and shipment to take three to four weeks after receipt of coil coated material.

II. Contract Documents

This proposal is based upon the following ASARCO Drawings:

<u>Drawing No.</u>	<u>Date</u>	<u>Structure</u>
A 7122	1/22/17	Wedge Roaster
A 7123	1/22/17	Wedge Roaster
B 7145	3/2/17	Fines Crushing
7149	2/27/17	Coarse Crushing
5180	6/11/36	Conv. Housing

III. Terms for Payment & Acceptance

- A. Materials: Net 30 Days upon arrival at place at which Buyer is to receive the material. The price payable hereunder is payable in Pittsburgh, PA., without deductions of any kind for taxes or licensing fees, or any changes, set offs, or counterclaims whatever.
- B. This offer shall terminate thirty (30) days from date hereof.

Statement of Exceptions Qualifications
and Requirements
Page Two

- C. This proposal is firm for shipment of all materials prior to December 31, 1979.
- D. This proposal is F.O.B. Wheatland, PA., with freight allowed to the jobsite.

IV. Materials

This proposal is based upon the following Steelite materials.

A) Wedge Roaster Building

- 1) Approximately 73 gross squares of Hi-Rib roofing with Corstan 400 finish in either 20 or 22 gage in either Corstan Tan or Corstan Sand finish.
- 2) Approximately 166 gross squares of Hi-Rib siding in 22 gage in either Corstan Tan or Corstan Sand finish.
- 3) One lot of 22 gage fabricated flashings with Corstan 400 finish in either Tan or Sand Color.
- 4) One lot Tremco No. 440 Sidelap Tape for the roof panels only.
- 5) One lot Hi-Rib Profile Neopreme Closures.
- 6) One lot of Size No. 14 #305 Stainless Steel Self-tapping Fasteners painted to match adjacent panels.

B) Fines Crushing Building

- 1) Approximately 48 gross squares of Hi-Rib roofing in either 20 or 22 gage with either Corstan 400 Tan finish or Corstan 400 Sand finish.
- 2) Approximately 162 gross squares of 22 gage Hi-Rib siding with either Corstan 400 Tan or Sand finish.
- 3) One lot of 22 gage fabricated flashings with Corstan 400 finish in either Tan or Sand Color.
- 4) One lot of Tremco No. 440 Sidelap Tape for the roof panels only.
- 5) One lot of Hi-Rib Neopreme Closures.
- 6) One lot of Size No. 14 #305 Self-tapping Fasteners painted to match adjacent panels.

Statement of Exceptions. Qualifications
and Requirements
Page Three

C) Coarse Crushing Plant

- 1) Approximately 73 gross squares Hi-Rib roofing with either 20 or 22 gage with either Corrtan 400 Tan finish or Sand finish.
- 2) Approximately 120 gross squares of Hi-Rib siding in 22 gage with either Corrtan 400 Tan or Sand finish.
- 3) One lot of 22 gage fabricated flashings in either Corrtan Tan or Sand Finish.
- 4) One lot of Tremco No. 440 Sidelap Tape for roof panels only.
- 5) One lot of Hi-Rib Neoprene Closures.
- 6) One lot of Fasteners painted to match adjacent panels.

D) Conv. Housing

- 1) Approximately 15 gross squares of Hi-Rib roofing either 20 or 22 gage with either Corrtan 400 Tan or Sand finish.
- 2) Approximately 17 gross squares of Hi-Rib siding in 22 gage with either Corrtan 400 Tan or Sand finish.
- 3) One lot of 22 gage of Fabricated flashings with either Corrtan Tan or Sand finish.
- 4) One lot of Tremco No. 440 Sidelap Tape for the roof panels only.
- 5) One lot of Hi-Rib Neoprene Closures
- 6) One lot of Size No. 14 #305 Self-tapping Fasteners painted to match adjacent panels.

V. Qualifications

- 1) Proposal includes no miscellaneous caulking other than the roof panel Tremco No. 440 Tape.
- 2) Proposal includes no miscellaneous iron or structural steel.
- 3) This proposal includes no fiberglass reinforced translucent panels.
- 4) This proposal includes no insulated wall panels.
- 5) This proposal includes no ventilators or louvers.

DAW Devate
About Now