

"ASBESTOS" STAKE IN DU PONT

- ☐ **Employee Health**
- ☐ **Removal Cost**
- ☐ **Liability**
- ☐ **Management**

DUP 0909346

DU 029008

5-2 Jan

PROPOSAL

- ☐ **"Asbestos" is an issue for which ERC should have value.**
- ☐ **Form Asbestos Focus Group (utilizing Asbestos Issues Committee and ERC Liaison).**
- ☐ **Review "Asbestos" issues outlined by A.I.C. and determine:**
 - If issues outlined are the right ones to work on.**
 - If groups identified to lead particular issue are right groups.**

DUP 0909347

DU 029009

ASBESTOS ACTIVITIES

CORPORATE (ERC/AIC)

- ☐ Develop policies, practices, etc. for Du Pont.
- ☐ Develop inspection/assessment guidelines for comprehensive program (document practices and options for EPA Neshaps compliance).
- ☐ Maintain network of resources throughout the Company.
- ☐ Redefine and continue lab QA/QC program.
- ☐ Maintain Corporate Respirable Fibers System.
- ☐ Update businesses/regions/sites on changes in regulations and best practices.

MLS

- ☐ Develop removal/contracting best practices - administration guideline.
- ☐ Develop integrated quality/cost abatement supplies program.
- ☐ Review and resolve contractor liability insurance issue.

BUSINESS

- ☐ Provide consultation and on-site inspection/management assistance to sites (options: Fibers, TIMS, MLS/vendors).

SITE

- ☐ Manage their own own asbestos program and coordinate training specific to their site.

DUP 0909348

DU 029010

PLANNING FOR THE INSPECTION

REVIEW OF PREVIOUS INSPECTION RECORDS AND BUILDING DRAWINGS

1. Scheduling of the Inspection
2. Obtaining Access
3. Building Record Review
4. Probable Homogeneous Areas According to Drawings
5. Consultation with Maintenance and Operations Personnel
6. Previous Inspection and Sampling Reports
7. Previous Abatement Records
8. Maintenance Records
9. Exclusions for Previously Performed Inspections (763.99)
10. General Planning Comments

DUP 0909465

DU 029011

1. SCHEDULING THE INSPECTION

Nights

Weekends

Business hours

School hours

Contract

DUP 0909466

DU 029012

2. OBTAINING ACCESS

Locks (keys)

Ladders/Lifts (Safety!!)

"Unused" or "Unimportant" spaces

Inaccessible spaces

Unknown spaces (dimensional accountability)

Contract

DUP 0909467

DU 029013

3. BUILDING RECORD REVIEW

Drawings

Specs

Construction contract

Bid documents (alternates)

Change orders

Pay requests (dates)

Construction field reports

Maintenance records

Original construction

Additions/Renovations

DUP 0909468

DU 029014

4. PROBABLE HOMOGENEOUS AREAS ACCORDING TO DRAWINGS

Design drawings

Contract document drawings

As-Built drawings

Shop drawings (Hyatt disaster)

Floor plans

Sections

Finish schedule

Mechanical/Plumbing/Electrical

Structural

DUP 0909469

DU 029015

5. CONSULTATION WITH MAINTENANCE & OPERATIONS PERSONNEL

Maintenance procedures

Maintenance schedules

Operations procedures

Operations schedules

M/P/E design/location/operation

"Unused" or "Unknown" spaces

Passed ACM disturbance

Current ACM procedures

O & M procedures?

Management sophistication

Employee sophistication

DUP 0909470

DU 029016

6. PREVIOUS INSPECTION AND SAMPLING REPORTS

Location and pattern of samples?

Number of samples?

Composition of samples?

Condition of ACM?

Type and use of ACM?

Other data applicable to AHERA

Assessment categories and your assessment
methodology?

Must be field verified

Do exclusions apply?

Are some samples applicable?

Must the entire survey be redone?

How was nonfriable ACM addressed?

Was any suspect ACM indicated?

DUP 0909471

DU 029017

7. PREVIOUS ABATEMENT RECORDS

Location

Methods

Disposal

Clearance criteria

Worker training

Residual contamination?

Urgent response action needed?

Special cleaning needed?

DUP 0909472

DU 029018

8. MAINTENANCE RECORDS

HVAC filter changes

TSI disturbance

O & M procedures?

Schedules

Routines

Emergency

DUP 0909473

DU 029019

9. EXCLUSIONS FOR PREVIOUSLY PERFORMED INSPECTIONS (763.99)

For homogeneous areas or sampling areas

Friable ACBM was identified

Nonfriable ACBM was identified

No ACBM is present (inspector)

No ACBM is present (lead agency)

Suspect ACBM is assumed ACM

All ACBM has been properly removed

No ACBM specified or used

Must assess friable

Has nonfriable become friable?

Must assess newly friable

READ THIS SECTION !!

DUP 0909474

DU 029020

10. GENERAL PLANNING COMMENTS

2 major divisions of suspect ACBM

Accessible Space

Inaccessible Space

Assumptions

Building conditions

Survey Conditions

DUP 0909475

DU 029021