

WHAT SHOULD YOU EXPECT FROM AN ASBESTOS ABATEMENT CONTRACTOR? .

Prior to the commencement of work

The contractor should provide documentation of satisfactory past abatement activity.

PLAINTIFF'S EXHIBIT

KRC-373

The contractor should submit proof that:

- 1) Only fully trained, highly skilled, and regularly employed personnel will be utilized for the project.
- 2) All personnel participating in the project are in full compliance with the mandatory medical surveillance provisions established by regulatory authorities.
- 3) Written respiratory protection program is in effect which meets the requirements of appropriate regulatory authorities. (reference ANSI Z88.2-1980)
- 4) The contractor is in compliance with the following:
 - a) All licenses required to handle asbestos have been obtained.
 - b) Each worker involved in the asbestos project must:
 - be declared by a physician to be capable of working while wearing a respirator.
 - have successfully completed a respiratory protection training course.

The contractor should submit a list of all equipment and supplies to be used on the project.

The contractor shall obtain all required permits and notify the EPA Regional Asbestos Co-ordinator (or their designee) and all other regulatory authorities as required by law. The notification shall consist of name and address of owner, description and location of project, scheduled start and completion dates, procedures to be employed, and disposal site.

Set-up

In general, the contractor must comply with:

- 1) The EPA National Emissions Standards for Hazardous Air Pollutants (NESHAPS) for the removal and disposal of asbestos materials. (Title 40, Part 61, Subparts A and M)
- 2) The EPA Friable Asbestos-Containing Materials in Schools. A Guidance Document. (EPA-450/2-78-014)
- 3) The EPA Guidance for Controlling Friable Asbestos-Containing Materials in Buildings. (EPA 560/5-83-002)