US REGULATIONS

(Continued)

CONSTRUCTION AND MARITIME STANDARD SUPPLEMENT (Continued)

Class of Work	Type of Work Covered by this Class of Work	Examples of Work Activity
Class IV Work	**"Contact", but not disturbance, of ACM or PACM** and cleaning up ACM and PACM waste and debris generated from Class I, II, or III activities.	*Popping-up ACM ceiling tile to look above if it is known that no asbestos debris is present on top of tiles *Clean-up after construction and/or installation activities have been performed *Installers laying cable where ceiling tiles and/or sprayed-on fireproofing contain asbestos, but there is no debris on top of the ceiling tiles, and hangers do not need to be installed *HEPA vacuum cleanup of a limited amount of asbestos debris not generated by other classes of work activities, and this is required as part of an installation or other construction related activity (example: sprayed-on fireproofing debris generated by air movement or vibration that needs to be cleaned up prior to the removal of a small number of ceiling tiles) *Custodial and maintenance personnel who are expected to contact ACM (such as floor tile). However, the training required under the general industry requirements is additionally required.
Asbestos impregnated asphaltic materials	**Removal or repairs to asbestos impregnated asphaltic materials**	*Removal or repairs to shingles, asbestos-containing built up roofing, intact roofing cements, mastics, and flashings *Removal or repairs to "incidental" roofing materials used for other purposes (such as asbestos impregnated asphaltic wrap used for protection of underground pipes)

This "Asbestos Awareness" course, if taken with the appropriate work practice training, is sufficient training to perform:

- Class III activities
- Class IV activities
- Working with asbestos impregnated asphaltic materials

This course, plus the appropriate work practice training is also sufficient training to perform:

- General Industry work activities