TORINO
ITALY

ASBESTOS CEMENT REQUIRES EXPERIENCE

We offer that experience we got by constructing and setting operating 50 complete plants all over the world.

SLURRY PREPARATION

Automatic dosage of the asbestos mix — Pneumatic asbestos transport — Asbestos fibre processing by Kollergang — Pneumatic transport and automatic dosage of cement — Slurry preparation by turbomixer — Normal and forced feed — Hydropulper — Water recuperators.

PIPE PLANTS

3-4-5-6 mts. pipe machines — Nom. diameters 50 to 1800 mms. with fully automatic equipment — Automatic and semi-automatic loaders for pipe machines — Central control board — Pipe maturing conveyor and tunnel — Automatic lathes for asbestos-cement pipes and joints — Automatic testing presses for pipes and joints.

SHEET PLANTS

Variable speed sheet machines with 2-3-4 sieve cylinders — Automatic cutting bench and pneumatic corrugators — Stacker — Sheet maturing tunnel — Rotating and bridge type Destacker — Mould lubricator.

We are not only a consulting office but we have been constructing exclusively machines for the asbestos-cement industry for 20 years.

R. C. M.

Corso P. Colletta 85 - Tel. 23.38.23 - Cable add. ERCIEM-TORINO
Telex 21307 - P.O. BOX 468 - 10100 TORINO