INDUSTRIAL INSULATION COMPANY

1893 East 55th Street
Cleveland, Ohio 44103
(216) 881-2141

679 Newton Street
Tallmadge, Ohio 44278
(216) 784-0437

CONSTRUCTION PURCHASING
JUN 21 9 53 AM '82

PLAINTIFF'S EXHIBIT
FD-1545b

June 17, 1982

Ref for 1/20 meeting

Ford Motor Co.
FMCC Building, Room 2425
The American Rd.
Dearborn, Michigan 48121

Attn: May Canning, Buyer

Ref: PIR-42-008784 - Insulation
Canton, Ohio

Dear Ms. Canning:

We are pleased to submit our quotation to remove the insulation as shown Column schedule of piping to be stripped of Asbestos pipe insulation attachment P.I.R. 008784, dated 4-16-82, pages 1 thru 6.

Also included in this quotation PIR 008784, dated 4-19-82, sheet #1 thru sheet #2 as prepared by Ford Motor Co. Engineering Dept., Canton, Ohio, Mr. Ray Denezak in charge.

Removal procedures as follows:

This insulation would contain asbestos due to the manufacturing date and installation prior to 1972.

Complete removal would be inaccordance with standards and procedure for handling asbestos waste as follows:

United States Environmental Protection Agency, National Emission Standards for asbestos, 40 CFR, Part 61, subpart B, Section 61-20, 61-25 and State of Ohio Environmental Protection Agency, Disposal procedure for Containerized Asbestos Waste.

Removal areas to be closed off to all outside personal not involved in the removal of the waste material.

Complete wetting down of the insulation during the actual removal.

All personal safety equipment furnished in accordance with standards.

All materials placed in double 6 mil plastic bags, properly labeled and placed in fiber drums which are labeled and inventoried.

Complete wet down and vacuuming of the area with proper EPA approved filter vacuum system.

INDUSTRIAL INSULATION COMPANY

1893 East 55th Street
Cleveland, Ohio 44103
(216) 881-2141

679 Newton Street
Tallmadge, Ohio 44278
(216) 784-0437

CONSTRUCTION PURCHASING
9 58 AM '82

Cont.

Waste disposal to approved EPA dumping site and recorded receipts to all parties of interest for proper disposal of asbestos waste.

Air monitering provided during removal and after clean-up.

Shower facilities hook-up to be provided to our employees by owner.

Reinsulation Procedure:

Areas of removal and areas requiring new pipe insulation installed will be insulated with Fiberglas pipe insulation as manufactured by Owens Corning. These thicknesses to be 1 1/2" or 2" to match the existing pipe insulation.

All rewrapping over the existing insulation to be of corrugated aluminum .016 with stenciled labels containing the message "Asbestos Insulation Under Corrugated Jacket."

Total and complete price per Ford Motor Co. specifications:

ONE HUNDRED FOURTEEN THOUSAND THREE HUNDRED SIX DOLLARS -- $ 114,306.00.

All work to be performed during normal working hours, Monday thru Friday, holidays excluded.

Alternate for consideration:

#1 - Deduct $ 15,400.00 if Ford Motor Co. furnished [illegible] 50 ft. Lift during the complete time of the contract.

#2 - Add to Base Bid $ 7,389.00 , if Color Coded Ceel-Co Jacket if used in lieu of aluminum jacket.

NOTES: #1 - No additional jacket included in Bid in areas where new pipe insulation is installed. Standard All Service Fire Retardent Jacket and Self Sealing Laps and stapled in place.

#2 - Dead lines as described shall be stripped of insulation only. No additional work included in this quotation for footage shown on PIR 008784, page #2, dated 4-19-82.

Premium Time?

8006 0275 PQ

PRODUCED BY FORD

CLARK

CONSTRUCTION
PURCHASING

JUN 17 5 55 PM '82

INDUSTRIAL INSULATION COMPANY

1893 East 55th Street
Cleveland, Ohio 44103
(216) 881-2141

679 Newton Street
Tallmadge, Ohio 44278
(216) 784-0437

Cont.

#3 - Should you require references of various Companies where we have removed asbestos pipe insulation and etc., we will be glad to submit to you if we are awarded the contract.

Should you have any questions regarding this quotation, please do not hesitate to contact me.

Thank you for your inquiry. Hoping to be of further service to you and your company.

Sincerely,
CLARK INDUSTRIAL INSULATION CO.

James W. Tatton

JWT:pt

8006 0276

PRODUCED BY FORD