

PPG INDUSTRIES

CHEMICAL DIVISION

BILL OF MATERIAL

MK. NO.	QUANTITY WANTED	QUANTITY RECEIVED	DESCRIPTION	CHARGE	PRICING	
					UNIT	EXT.
	10.4		CUBIC YD. OF EARTH FILL TO BE MOVED INTO PLACE			
			LABOR FOR THE ABOVE			
7	440		SQ. FT. OF NEW LIGHT-DUTY WOOD FRAME SUB-FLOOR. SUB-FLOOR WILL BE COVERED W/TILE UNDER LATER WORK NUMBER			
			MATERIAL			
			LABOR			
8	7073		50 FT. OF $\frac{1}{8}$ " THICK VINYL ASBESTOS TILE FLOOR COVERING AS FOLLOWS...			
			MAT'L 7073 $\text{ft}^2 @ 0.35 \$/\text{ft}^2$		2476	
			LABOR 7073 $\text{ft}^2 @ 0.15 \$/\text{ft}^2$		1081	

PPG INDUSTRIES

CHEMICAL DIVISION

BILL OF MATERIAL

M.K. NO.	QUANTITY WANTED	QUANTITY RECEIVED	DESCRIPTION	CHARGE	PRICING	
					UNIT	EXTEN
			WALL INSULATION (LABOR + MAT'L)			
			8828 ft ² @ 0.11 \$/ft ²		971 ⁰⁰	
			BIRCH PANELING (LABOR + MAT'L)			
			5653 ft ² @ 0.55 \$/ft ²		3109 ⁰⁰	
			PLYWOOD SHEATHING (LABOR + MAT'L)			
			14,214 ft ² @ 0.36 \$/ft ²		5117 ⁰⁰	
			PAINTING SHEATHING (LABOR + MAT'L)			
			14,214 ft ² @ 0.06 \$/ft ²		853 ⁰⁰	
12.			MODIFY EXISTING DOOR-WAY			
			IN NORTH WALL OF K-307			
			IN ACCORDANCE W/ ATTACHED			
			SKETCH			