

COPIES:

P.B.Proctor-GHQ
 D.H.Lyons-GHQ-(3)
 J.Q.Trice-Research
 F.T.Petersen-DEQ
 O.H.Schlemmer-Waukegan
 L.L.Trauth-Marrero
 J.M.Woodward-Stockton
 C.Stelchek-Denison
 H.F.Kahlen-Long Beach
 File

 QUALITY CONTROL DEPARTMENT
 TRANSITE PIPE DIVISION

 JOHNS-MANVILLE
 MANVILLE FACTORY

REPORT NO: TP-8611

DATE:

3/20/61
 Also coming
 have we been shipping
 samples from incoming
 blue fiber to manville?
 CJS
 3-2-61

Subject: Asbestos Blue Fiber
 Requested by: F. T. Petersen
 Identification: Asbestos Fiber Specification and Control Procedures
 F. T. Petersen's Letter of 10/9/59

SUMMARY:

As requested in subject letter, McNett testing of Asbestos Blue Fiber, submitted by all locations, were conducted by the Manville Pipe Division Control Laboratory.

Two of the five composite samples submitted were tested and the averages of these tests are being reported.

Where shipments were divided, only the first samples submitted were tested.

DATA:

JM Test Method 411:2 (McNett Wet Classification):



Ship Name	Location Sampled	Fiber Type	Date Recd.	Tested at Manville	+14 Mesh		+28 Mesh	+100 Mesh	-100 Fines	Water Temp.
					Fiber	Rock				
SS Kwangs1	Stockton	A Blue	1/4/61	1/17/61	70.1	0.3	2.3	2.2	25.1	48°
SS Aimee Lykes	Waukegan	A Blue	1/5/61	1/10/61	69.5	0.2	2.9	2.8	24.6	50°
SS Almeria Lykes	Waukegan	A Blue	1/5/61	1/17/61	69.4	0.2	2.6	3.2	24.6	48°
SS Golden Bear*	Stockton	A Blue	2/14/61	2/16/60	68.3	0.0	2.5	2.0	27.2	48°
SS Gorgon	Long Beach	A Blue	2/15/61	2/15/60	70.1	0.1	2.9	2.5	24.4	46°

*Passes Tentative Specifications

See W. L. VanDerbeek's Letter Dated 2/20/61 (Transhipped from SS Kwang Tung)

Purchase Specifications - %:

Minimum

69.0

Maximum

3.0

25.0

003226

APPROVED BY: F. Hardenstein

REPORT BY: J. Dooley