

INSULATION REPAIRS AT ACID PLANTWORK SHEET

Furnish all labor, material and equipment including scaffolding for insulation repairs at El Paso Acid Plant.

Jacketing to be 0.016 and 0.020 aluminum with stainless steel banding.

Manhole jacketing to be 304 stainless steel or equal, 16 gage.

1. Five Manhole Covers
2. Twelve Feet Of 30" Pipe
3. Repair Jacketing On Flange
4. 78" Expansion Joint
5. 60" X 48" Jacket Repair
6. 12" Jacket Repair On Pipe
7. 40" Manhole Repair
8. Replacement Of Jacketing On 45" And 78" Pipe
9. Repair Insulation On Valve Bonnet
10. Repair On Vessel 36" X 40" X 3"
11. Repair On 78" Pipe
12. Repair Loose Jacket On Flange
13. Repair On 48" Manhole And Top Of Vessel
14. Repair Bottom Half 24" X 60" Manhole Cover.

October 18, 1976

Labor Material and Scaffold
Alternates for Aluminum and S.S. Jacketing

- 1 5 Manholes
- 2 12' of 30" Pipe
- 3 Repair metal on flange
- 4 Expansion Joint - 78"
- 5 60" x 48" Repair of Metal
- 6 12" Metal Repair on Pipe
- 7 40" Manhole
- 8 Replace Metal on 45" and 78" Pipe
- 9 Repair Valve Bonnet Insulation
- 10 Repair on Vessel 36" x 40" x 3"
- 11 Repair on 78" Pipe
- 12 Repair loose metal on flange
- 13 48" Manhole and top of vessel

Sept. 30, 1976

ALL TEMP

CONTRACT 1110⁰⁰

PD1622 1350⁰⁰
2460⁰⁰

Pay in May

3-23-76
470⁰⁰ #1 EXCH
HDD 3" ON BOTTOM

4-1-76
1350⁰⁰ #24 & 28
3" ON BOTTOM

Carla Escobar
778-6948