

<u>Area to be sampled</u>	<u>Number of samples</u>	<u>Minimum sample volume in liters</u>
Work area	4	60
Outside work area barriers	2	120
Outside building	2	240

Samples will be taken after the actual removal operation has begun.

8. Clean-up and Guarantee

- a. After the second cleaning operation the following test should be performed: A complete visual inspection should be made to insure dust free conditions, and two air samples within 48 hours after completion of all cleaning work should be taken. (Minimum volume of air sample 240 liters).
- b. If noncompliance occurs, repeat cleaning and measurement until space is in compliance. Refer to 29 CFR 1910.1001, 7a.

9. Disposal of Asbestos Material and Related Debris

- a. All asbestos materials and miscellaneous debris in sealed drums will be transported to the predesignated disposal site in accordance with the guidelines of the U.S. Environmental Protection Agency.
- b. Workers unloading the sealed drums and machinery operators will wear respirators when handling material at the disposal site.