FILE NAME: Allied Signal Bendix (ASB)

DATE: 0000

DOC#: ASB055

DOCUMENT DESCRIPTION: Excerpt - Internal Report - Bendix Brakes for Ford Vehicles Workplace Simulation Demonstration

PLAINTIFF'S EXHIBIT Bx 5032

BENDIX BRAKES FOR FORD VEHICLES

WORKPLACE SIMULATION DEMONSTRATION

Prepared by:

Richard L. Hatfield
William E. Longo

Materials Analytical Services, Inc.
Norcross, Georgia

Raleigh Office:
916 Hutton Street • Suite 101
Raleigh, NC 27606
(919) 829-7041 • FAX (919) 829-5518

Atlanta Office:
3597 Parkway Lane • Suite 250
Norcross, Georgia 30092
(770) 448-3200 • FAX (770) 368-8256

Bendix Brakes for Ford Vehicles
Filing Demonstration
Asbestos Air Analysis Results

Sample #	Sample Description	PCM Fibers/cc	TEM (All) Structures/cc	TEM ≥ 5.0μm Fibers/cc
I-I-A	IWA Background	<0.002	<0.026	N/A
I-I-B	IWA Background	0.003	<0.026	N/A
1-II-A	IWA Area	overloaded	9,535	482
1-II-B	IWA Area	2.92	1,156	96
I-III-A	RHL - Personnel	5.47	3,042	285
I-III-B	RHR - Personnel	6.89	10,561	1,162
I-III-C	WLL - Personnel	6.22	3,318	<98
I-III-D	WLR - Personnel	6.01	4,087	475

		Structures/sq.ft	Structures/cm^2
I-IV-A-RH	Fabric	177 Million	190 Thousand
I-IV-B-WL	Fabric	3.0 Billion	3.2 Million
M18837-1	Dust from Inside Brake Box	2.9 Billion	3.1 Million

Bendix Brakes for Ford Vehicles
Clean-up After Filing Demonstration
Asbestos Air Analysis Results

Sample #	Sample Description	PCM Fibers/cc	TEM (All) Structures/cc	TEM ≥ 5.0µm Fibers/cc
II-I-A	IWA Background	<0.003	<0.03	N/A
II-I-B	IWA Background	0.003	<0.03	N/A
II-II-A	IWA Area	4.14	42,312	3,193
II-II-B	IWA Area	3.65	14,897	2,573
II-III-A	RHR - Personnel	12.26	29,114	3,957
II-III-B	RHL - Personnel	12.20	14,967	2,225
II-III-C	WLR - Personnel	12.67	13,454	2,374
II-III-D	WLL - Personnel	8.26	3,792	798

		Structures/sq.ft	Structures/cm^2
II-IV-A-RH	Fabric	100 Million	108 Thousand
II-IV-B-WL	Fabric	149 Million	161 Thousand