PLAINTIFF'S EXHIBIT
CT-1054

BILL OF MATERIAL
MATERIAL FOR ONE

A_3 REQ'D	A_2 REQ'D	A_1 REQ'D	PART No.	PART	MATERIAL
	X		1	TRACK SUPPORT	WELDMENT
	1		2	TIE PL	1/2 x 10 C1020 HRS
	1		3	BRACKET	3 x 5 3/4 C1020 HRS
	1		4	SUPPORT	8 LI 18.75# HRS
	2		5	BLOCK	1 1/4 x 2 C1020 HRS
			6	BLOCK	2 x 2 3/4 C1020 HRS
			7	SHAFT	2 1/2 OD. C1018 COLD DRAWN SIL.
X			8	COLUMN	WELDMENT
1			9	TOP PL	1/2 x 4 C1020 HRS
1			10	COL.	6 x 4 LIGHT BEAM 12# HRS
1			11	BASE PL	1/2 x 6 C1020 HRS
			12	SPACER	4 3/8 D C1020 HRS
			13	PIN	1/2 DIA. C1018 C.F.S.

REF.

MANDREL PIPE TRANSFER ASS'Y. ——— DWG. 17E-8291 ✓

MANDREL TRANSFER SUPPORT ASS'Y. ——— DWG. 18K-8465 ✓

S. A. No.

JOB No.

KEASBEY & MATTISON CO.
AMBLER, PA.
CENTRAL ENGINEERING DEPARTMENT

SYMBOL
EWA 411

MANDREL TRANSFER SUPPORT DETAILS
13' PIPE MACHINE
A.C. PIPE PLANT #7

DR. G.K.	APP. JJH	CK.	APP.	DATE 8-2-61	SCALE 6"=12"=1'-0"

THIS DRAWING IS THE PROPERTY OF AND MUST NOT BE USED IN ANY MANNER DETRIMENTAL TO
KEASBEY & MATTISON CO.
IT IS ONLY LOANED SUBJECT TO RECALL AT ANY TIME

PRINT ISSUED

ISSUE

DWG. No.
8466

CTD028886