WORK DESCRIPTION

REMOVE CHLORINATOR BASKETS

DEPARTMENT 246

BUILDING CR

ESTIMATE NO. 3583

WORK ORDER NO. 2-3256

TSD JOB NO. 91370:3198
3362

TECHNICAL SERVICES DEPARTMENT

MONSANTO COMPANY

W. G. KRUMMRICH PLANT

MONSANTO, ILLINOIS

Prepared by:

C. E. Woodward
November 1, 1966

W RK REL N [illegible]256

1 General

a. This job provides for removal of chlorinator baskets from Nos 1, 2, 3, and 4 chlorinators.

b The large crane will be utilized and the procedure should be similar to the existing procedures for basket removal and repair

2 Building Work

None

3 Equipment

a Visual inspection of each chlorinator will be made by the product [illegible] foreman and additional work necessary to provide the department with reliable units will be charge as true repair

4 [illegible]

None

5 Structural and Fabrication

None

6 Piping Work

a [illegible] as necessary to complete the job

7 Electrical Work

None

8. Instrumentation

None

9. Insulation

a. Replace or renew insulation removed or damaged during the job.

MONS 034939

10. Miscellaneous

a. Safety - Aroclor is a toxic hazard; however, at atmospheric temperature and in an open area, no side effects should be experienced by the workers. Care should be taken to avoid prolonged exposure to the concentrated atmosphere of the chlorinator shell.

MONS 034940