OFFICE COPY

UNION CARBIDE CORPORATION
OLEFINS DIVISION
ENGINEERING DEPARTMENT

Box
511-2

CONSTRUCTION SPECIFICATIONS

FOR

TEXTILE FIBERS LABORATORY
BUILDING 10,727

Technical Center
South Charleston, West Virginia

TECHNICAL CENTER
SOUTH CHARLESTON, WEST VIRGINIA

PLAINTIFF'S EXHIBIT
76027.00

UCASB00234669

SECTION 15-C

THERMAL INSULATION

1. SCOPE OF WORK

A. The work under this Division includes the furnishing of all supervision, labor, materials, tools, and equipment necessary for, and incidental to, application of all thermal insulation as shown or called for on the Drawings, and specified in the Owner's insulation Specifications.

B. The following items of related work are included in other divisions of these specifications:

(1) Roof insulation, Division 7, Section A.

2. RESPONSIBILITY FOR MATERIALS

A. The Contractor shall furnish all materials.

3. MATERIALS

A. Insulation materials shall be in accordance with Owner's Specifications 10L, 14J, 15H, 17RX, 18 FX, and 23H, which are included and made a part of these specifications.

4. APPLICATION

A. Insulation shall be applied in accordance with instructions and details given in the numbered Insulation Specifications in Paragraph 3 and the General Insulation Specifications which are included and made a part of these specifications.

B. Type and thickness of insulation shall be as shown or called for on the Drawings.

C. Insulation shall not be installed until after respective piping systems have been tested and approved. Where Contractor does otherwise, it shall be his responsibility to remove and replace the insulation at his own expense.

UCASB00234837