CHEVRON U.S.A. INC.
ENGINEERING & MAINTENANCE DEPARTMENT

SPECIFICATION NO. EP-289-N
FEBRUARY 10, 1977

PLAINTIFF'S EXHIBIT
CHV-691

SPECIFICATION NO. EP-289-N
REPAIR DAMAGED AND REPLACE MISSING INSULATION IN ALL PLANTS

1.0 SCOPE

This specification covers the repair and replacement of insulation and weathercoating on various sizes of pipe and fittings throughout the refinery per the attached work list.

2.0 DETAILS OF THE WORK

2.1 Contractor will repair or replace insulation per Standard Drawings GA-N99783-3 and GB-N99993-0 and as directed by our Company Representative.

2.2 Contractor will clean up and dispose of daily, all debris and trash created by the work being done.

3.0 GENERAL PROVISIONS

3.1 Contractor shall comply with the attached Refinery Instruction No. 1404 and ascertain the pertinent Refinery Safety Regulations from Company's Field Representative before commencing work.

3.2 Contractor shall obtain permission daily from Unit Operator before starting to work in any plant.

4.0 MATERIALS

4.1 All insulation specified in Standard Drawings GA-N99783-3 and GB-N99993-0 shall be asbestos free.

4.2 Aluminum jacketing shall be epoxy coated.

5.0 FURNISHED BY COMPANY

Company will provide a site within the refinery for trash disposal.

6.0 FURNISHED BY CONTRACTOR

Contractor shall furnish all labor, tools, equipment, expendable materials and service necessary to complete the work set forth in this specification.