ATI
# ASBESTOS TESTING INC.
5205 NOYES AVE. • CHARLESTON, WV 25304 • (304) 925-6795

November 18, 1986

Erik A. Osby
Industrial Hygiene Dept.
Union Carbide Corporation
P.O. Box 2831
Charleston, WV 25330

The following bulk insulation analysis pertain to samples received on 11/14/86. All bulk insulation analyses are performed in accordance with EPA recommendations concerning analysis of bulk insulation using Polarized Light Microscopy.

## ANALYSIS RESULTS

Sample #1

| | |
|---|---|
| Roofing material-Bldg. 190 | 70%-Asbestos (Chrysotile)<br>30%-Epoxy Resin |

Sample #2

| | |
|---|---|
| Ceiling material, womens' bathroom-Bldg. 190 | N.D.-Asbestos*<br>5%-Cellulose<br>95%-Gunnite Clay |

Sample #3

| | |
|---|---|
| Material deposited on compressor-Bldg. 190<br>11/13/86 | N.D.-Asbestos*<br>5%-Mineral Wool<br>5%-Synthetics Fibers<br>35%-Dirt<br>55%-Paint |

Sample #4

| | |
|---|---|
| Ten inch pipe insulation (mid-section)-<br>Bldg. 308 | 15%-Asbestos (Chrysotile)<br>85%-Clay |

Sample #5

| | |
|---|---|
| Verticle steamline insulation from hallway<br>in mid-section of Bldg. 308 | 35%-Asbestos (Chrysotile)<br>65%-Clay |

Respectfully submitted,

A03986

John S. Ferrell
Industrial Hygienist

*N.D. denotes none detected.