EASTERN Refractories Co., Inc.

20 FLANDERS ROAD, BELMONT, MASS. 02178 ... Telephone IVANHOE 9-0700

REFRACTORIES — INSULATIONS — CORROSION PROOFING
CONTRACTORS — DISTRIBUTORS

PLAINTIFF'S EXHIBIT
WH-866

ADDRESS REPLY TO
P. O. Box 156
Belmont, Mass. 02178

PROPOSAL

Date June 4, 1969
Page 1 of 2
Quotation No. 10437

Robert A. Keasbey Company
139-149 West 19th Street
New York, New York 10011

ATTENTION: Mr. Paul Tutshulte

SUBJECT: Blankets for Westinghouse Appurtenances
Indian Point Nuclear Station
Buchanan, New York

Gentlemen:

We are pleased to submit our estimate for furnishing the material and fabrication of the following blankets.

Blankets for Cross-over piping - Dwg. 719-J-662 -

Item 7	12	1/2 Blankets	19" x 64" x 3" thick
Item 8	12	1/2 Blankets	8" x 54" x 3" thick
Item 9	12	1/2 Blankets	3" x 54" x 3" thick
Item 10	12	1/4 Rings	20.5" x 54.5" x 3" thick
Item 11	6	Blankets	12.76 x 15" x 3" thick
Item 12	6	1/2 Blankets	4.5" x 76" x 3" thick

+ other covers ?

Blankets for Cross-under piping - Dwg. 719-J-667 -

Item 7	8	1/2 Blankets	19" x 60" x 2-1/2" thick
Item 8	8	1/2 Blankets	2-1/2" x 52" x 2-1/2" thick
Item 9	8	1/2 Blankets	8" x 52" x 2-1/2" thick

Main Steam Inlet Piping - Dwg. 721-J-210 -

Item 9	2	Blankets	32.5 Diam. x 3" thick

(over)

Price As detailed herein.

Terms Net 30

This proposal is subject to the terms and conditions on the reverse side of this page.

Respectfully submitted,
EASTERN REFRACTORIES CO., INC.
By Albert L. Sargent
Albert L. Sargent

ALS/mkm
In duplicate

PROPOSAL

Robert A. Keasbey Company

Item 10	2 Blankets	12-1/2" x 112" x 3" thick
Item 11	2 Blankets	7" x 65" x 3" thick
Item 12	2 Blankets	17.5 Diam. x 3" thick
Item 13	2 Blankets	31.5 x 117" x 3" thick
Item 14	4 Blanket Rings	34.24 Diam outer) x 3" thick 22.00 Diam inner)
Item 15	2 Blankets	12" x 148.88" x 3" thick
Items 16 and 17	8 1/4" Rings	13" x 31.5" x 3" thick

Blankets will be built up with successive layers of ERCO-Mat to thicknesses specified and enclosed with AA Asbestos Cloth to meet Westinghouse Material Spec. 41511 Specification 600359 - Part 1.

Blankets will be quilted at 6" o.c. as specified and furnished with Cadmium plated ERCO Bergen Hooks and Washers to provide securements for proper installation.

Our estimate is based on the use of Hog rings for the final outside seams of all pads.

Our price for this schedule of prefabricated blankets will be the sum of $6,580.00, shipped freight allowed to Indian Point Station, Buchanan, New York.

For the ERCO-Mat material only called for in Item 21 - Symbol C - Dwg. 721-J-210, we have figured on sixteen (16) Rolls @ 225 sq. ft. per roll or 3600 sq. ft. @ 0.64 per sq. ft., or a total of $2,304.00 freight allowed to Indian Point Station, Buchanan, New York.

- - - -