



SELLE INSULATION COMPANY

Houston

7344 Stiles
El Paso, Texas 79915
(915) 772-8525

Lubbock

PLAINTIFF'S EXHIBIT

ASA-1260

April 22, 1983

ASARCO, Inc.
P.O. Box 1111
El Paso, Texas 79946

Attn: Mr. Carl Glaser

RE: Antimony Plant Conversion
2- Chamber Baghouse and Ductwork

Gentlemen:

We are pleased to submit our bid on the above referenced project. We propose to furnish and install the thermal insulation and jacketing as follows:

1. Baghouse Sides, Top, and Hoppers
3" thick mineral wool secured with 10 gauge weld pins between stiffener ribs. .016 corrugated aluminum sheets shall be screwed to the stiffener ribs. We have assumed that the space between each baghouse will not be filled; however, the two baghouse modules will be "boxed-in" with insulation and jacketing.
2. New Ductwork and Repair of Existing Ductwork
3" thick mineral wool secured to the duct in a similar fashion as the baghouse. The metal finish will match the existing. Expansion joints, butterfly dampers, and access doors will be left open.

NET PRICE FOR ITEMS 1 AND 2

\$20,500.00

We have figured in all of our own scaffolding. This price is based on no overtime work.

If you have any questions, please call me at 772-8525. We look forward to serving you again.

Sincerely,

SELLE INSULATION COMPANY

Randy Hutton
Contract Manager

RH/djb

COMMERCIAL / INDUSTRIAL / LOW TEMPERATURE / METAL BUILDING INSULATION / ROLL RUNNER

ASARCO ELP 0009933

TEMP CON INC

INSULATION & SPECIALTY
CONTRACTORS

3518 DURAZNO AVE.
EL PASO, TX. 79905

EL PASO, TX. (915) 544-2937
THIBODAU, LA. (504) 447-5615 (24 HRS.)
HARVEY, LA. (504) 348-9525
LAFAYETTE, LA. (318) 981-8434

April 6, 1983

Asarco Inc.
P. O. Box 1111
El Paso, Texas 79999

Attention: Mr. Carl Glaser

Reference: Anitmony Plant Conversion

Temp-Con, Inc. Proposal Number: 144/83

Dear Sir:

We are pleased to offer this proposal to insulate and weather-proof the new bag filters, cone's, transitions, duct and piping associated with the above referenced project.

We propose to furnish all labor, tools, equipment, scaffolding, materials, insurance and supervision to complete our portion of the project.

Our proposal is in strict accordance with drawings and specifications furnished. All materials will match existing equipment, duct and etc.

Our lump sum price to perform the above work is \$19,800.00.

We would also propose to remove and replace insulation as required on a T/M basis. All materials required will be invoiced at our cost plus 17%. All labor will be invoiced at our standard rates which are on file with Asarco.

We sincerely appreciate this opportunity to quote on your insulation requirements and are looking forward to working with you on this and future projects.

Yours very truly,

Fred N. McGehee Sr.

Fred N. McGehee, Sr.

FNM/klw

B.H. & new user only



ASARCO ELP 0009934

ALL TEMP INSULATION CO.

Sales and Contracting

3200 Gateway East
El Paso, Texas 79905
(915) 533-1910

April 20, 1983

ASARCO Company
P.O. Box 1111
El Paso, TX 79999

Re: Antimony Plant Conversions
2 bags

Gentlemen:


We propose to insulate the above referenced project for the total sum of \$29,000.00.

The project will be insulated in strict compliance with the owner's specifications.

The insulation shall be 3" fiberglass and the finish will be .016 aluminum jacket, matching the existing one.

We also propose to replace any damaged insulation for \$9.65 per square foot. We also propose to remove only, any insulation required to be removed for \$12.00 per hour.

Very truly yours,



Carlos R. Escobar

INSULATION & SPECIALTY
CONTRACTORS

**TEMP
CON
INC**
3518 DURAZNO AVE.
EL PASO, TEXAS 79905

EL PASO, TX. (915) 544-2937
THIBODAUX LA (504) 447-5615 (24 HRS.)
HARVEY LA (504) 348-9525
LAFAYETTE LA (318) 981-8434

November 9, 1982

Asarco Inc.
P. O. Box 1111
El Paso, Texas 79999

Attention: Mr. Carl Glaser

Reference: Time and Material Quotation

Temp-Con, Inc. Proposal Number 362/82

Dear Sir:

We are pleased to offer this proposal for your consideration to perform time and material work in your plant.

<u>LABOR RATES</u>		
<u>CLASSIFICATION</u>	<u>STRAIGHT TIME</u>	<u>OVERTIME</u>
Superintendent	\$27.50	\$37.40
Foreman	\$20.00	\$27.20
Mechanic	\$17.00	\$22.50
Helper	\$10.50	\$14.50

The above rates include base labor, payroll taxes, insurance, overhead and profit.

Overtime is time in excess of eight hours per day and all work on Saturdays, Sundays, and plant observed holidays.

MEMBER OF
NICA
National Insulation
Contractors Association

ASARCO ELP 0009936

ASARCO ELP 0009931

BID TABULATION
Form # PD 8-B Revised 9 60

EQUIPMENT -

Autism, BAG House & Oct Insulation

DATE _____

4-25-81

APPRO. #

REC'D. #

PREPARATION - SEE INSTRUCTION SHEET & PURCHASE MANUAL SECTIONS B-2 & C-2.

DEP'T. - _____ BY _____ Page _____ of _____ Pg'