PLAINTIFF'S EXHIBIT

BIR-530

Rec'd 7/12/77

OVERALL PAINT, INC. OFFICE & PLANT: 26200 RICHMOND ROAD • BEDFORD HEIGHTS, OHIO • Telephone: 292-602

DIRECT MAIL TO: BOX 22233, CLEVELAND, OHIO 44122 • Area Code 21

July 7, 1977

Bird & Son
P. O. Box 360
Franklin, Ohio 45005

Attn: Mr. David K. Morris

Dear Mr. Morris:

Thank you very much for forwarding along the roof coating and cement specifications.

As you are probably aware, the roof coating and cement specifications that you sent to me were actually copies of the original specifications or formulations provided to us by the Logan Long Company. Over the years, by mutual agreement, the formulations were changed as various materials became more difficult to obtain, more expensive, and it was decided that some of them added nothing to the product.

I am returning, herewith, an updated formulation or specification list and I have also added information on the aluminum roof coating and asphalt emulsion which we provide to you, but which has been made under our basic formulations.

If you require any additional information or if we can be of further help, please do not hesitate to call on us. Thank you, once again, for your cooperation in the above matters.

Kindest personal regards,

OVERALL PAINT, INC.

M. A. DAVIS

MAD/rv

July 7, 1977

BIRD & SON COMPANY

ROOF COATING & CEMENTS SPECIFICATIONS

PLYWELD CEMENT

700 lb. Asbestos
200 lb. Limestone
450 lb. Resin Solution
300 Gal. Lap Cement
300 Gal. Sohio Grade-U Asphalt Cut-Back (fast Setting)

PLASTIC CEMENT (ROOF DOKTOR)

590 Gal. Sohio Grade-B Asphalt Cut-Back
1100 lb. Asbestos, 7M (Manville)
400 lb. Crushed Limestone
20 lb. Acid or Chlorinated Paraphin

FOUNDATION COATING

Asphalt Roof Coating ("Roof-Tonic", Green Label)
SealAll Coating
100% Sohio Grade-B Asphalt Cut-Back

FIBRE ROOF COATING (ROOF-TONIC - BLUE LABEL)

650 Gal. Sohio Grade B Asphalt Cut-Back
350 lb. Asbestos 7M (Manville)

SUPER CEMENT

1000 lb. Asbestos 7M (Manville)
220 Gal. Sohio Grade-A Lap Cement
405 Gal. Sohio Grade-B Asphalt Cut-Back

ASPHALT PRIMER

Sohio Grade-B Asphalt Cut-Back

DRIVEWAY SEALER (Dura-Top)

100% Sohio Grade-A Asphalt Cut-Back

(Cont next page)

BIRD & SON CO. ROOF COATING & CEMENTS SPECIFICATIONS (CONT.)

SILVERON ALUM COATING

Vehicle	75%
Asphalt Cutback	40%
Gilsonite Solution	6%
Petroleum Resins	5%
Petroleum solvents	49%
Pigment	25%
Aluminum Pigment Paste	75%
Asbestos Fibre	25%

FIBRED EMULSION #405

U.S. Specification MIL-R-3472