C-15-060-8

PLAINTIFF'S EXHIBIT CHV-165

SATCO, IN

Refractory and Corrosion Proof Systems

P. O. BOX 80023
BATON ROUGE, LA. 70898

504/291-0352

MEMO

TO KEVIN WALKER

CHEVRON. EL PASO, TEXAS | 3196-3-2

SUBJECT Fiber REPAIRS in FURNACE | DATE 7-25-83

We propose to REMOVE All loose CASTables discussed and REPAIR in the following MANNER: CHEVRON is to weld 304 SS - 6" INSULTWIST PINS in designated by us AREAS. After this is done, A coat of SAIRSET will be ~~placed~~ applied to surface to be insulated. THREE (3) layers of two (2) inch blanket will be INSTALLED And SECURED by the pins And WASHERS provided by us. After All blanket is INSTALLED, A SPRAY coat of "Ridgedizer" will be applied for wind - RESISTANCE PURPOSES. All CRACK - PACKING will be done with loose bulk ~~KAOWOOL~~ SIGNED And A SAIRSET MORTAR MIXED IN to REPLY INSURE A good bond. Note: Ridgedizer WAS NOT INCLUDED IN the first quote, PLEASE MAKE An Adjustment of $85.00 including labor time if Ridgedizer is required. Total Cost $3,885.00 JKW

DATE | SIGNED

☐ NO REPLY NECESSARY ☒ PLEASE REPLY ☐ TELEPHONE ☐ RETURN ENCLOSED MEMO WITH REPLY

~~BAFFLE WALLS: TO REMOVE AND REPLACE BOTH BAFFLE WALLS~~ IN THE MANNER DISCUSSED IN THE FURNACE (6" INWARD) THE COST TO CHEVRON IS FOR ALL LABOR, SUPERVISION, & MATERIALS COME TO $12,200.00

CHEV B8 5676