PLAINTIFF'S EXHIBIT

FD-1561 J

Inter Office

Transmission and Chassis Division
General Office

January 4, 1984

To: Mr. P. H. Allen
Mr. J. R. Houser
Mr. J. J. Kaniewski
Mr. S. P. Manzella
Mr. G. L. Powdrill
Mr. T. L. Snider
Mr. G. W. Williams

cc: Mr. R. L. Coosaia
Mr. M. R. Craig
Mr. A. Jurcisin
Mr. E. C. Koops
Mr. T. M. McCaffrey
Mr. A. E. Phelps
Mr. J. M. Poe
Mr. K. W. Watler

From: R. L. Smith

Subject: T & C Divisional Asbestos Plan

Attached is a survey guide to help in defining the magnitude of asbestos concerns in your Plant. As discussed at our December 1, 1983 meeting, a field check and judgmental decision on the condition of asbestos coverings for equipment, piping and building is the initial step in arriving at a corrective program.

Identification of existing conditions and possible solutions will be the primary items of discussion at our upcoming meeting. Our next meeting will be March 1, 1984 at the Division Plant Engineering Office.

R. L. Smith

HWS:bg
Attachment
MB12-6

8006 0419

PRODUCED BY FORD

"PRELIMINARY"

ASBESTOS SURVEY:

Where should we look for asbestos and what are we likely to find and what should we do about it?

Where to Look?	What Will We Find?	What To Do?
Boilerhouse	. Asbestos on steam, condensate, condenser lines.	. Encapsulate above truss* & remove below.
	. Asbestos on condensate tanks and controls.	. Remove/replace
	. Boiler fire box & doors.	. Remove/replace
	. Flue gas breeching & related ducts.	. Remove/replace
Condensate Stations in Plant	. Asbestos on lines and tanks.	. Remove/replace.
Drops to restrooms and Water Heaters.	. Asbestos on lines and tanks.	. Remove/replace.
In-Plant Overhead	. Asbestos on lines.	. Encapsulate above truss*.
Industrial Washers.	. Asbestos on lines.	. Remove/replace only for safety (hot metal contact).
Heat Treat	. Asbestos on door seals, very little on furnace exterior.	. Replace with non-asbestos.
	. Insulation behind fire brick.	. Replace when rebuilding.
General Use	. Weld blankets, gloves	. Replace with non-asbestos.
Large H & V	. Asbestos on steam lines.	. Replace in areas where people are servicing equip/ & encapsulate other areas.
Small Unit Heaters	. Asbestos on steam lines.	. Encapsulate above truss line* & remove/replace below.

MS11-93

8006 0420

Where to Look?	What Will We Find?	What To Do?
Office Areas	. Asbestos in ceiling tiles.	. Remove/replace.
	. Asbestos in ducts.	. Remove/replace.
	. Asbestos as roof/ceiling insulation.	. Remove/replace.

*Any item, valve, etc. which will require frequent service should be isolated 10 feet on each side by non-asbestos insulation.

Plant Engineering
12/14/83

MS11-93A

8006 0421

PRODUCED BY FORD