

# EASTERN

*Refractories Co., Inc.*

20 FLANDERS ROAD, BELMONT, MASS. 02178

Telephone IVANHOE 9-0700

REFRACTORIES — INSULATIONS — CORROSION PROOFING  
CONTRACTORS — DISTRIBUTORS

ADDRESS REPLY TO  
P. O. Box 156  
Belmont, Mass. 02178

## PROPOSAL



Date June 4, 1969  
Page 1 of 2  
Quotation No. 10437

Robert A. Keasbey Company  
139-149 West 19th Street  
New York, New York 10011

ATTENTION: Mr. Paul Tutshulte

SUBJECT: Blankets for Westinghouse Appurtenances  
Indian Point Nuclear Station  
Buchanan, New York

Gentlemen:

We are pleased to submit our estimate for furnishing the material and fabrication of the following blankets.

Blankets for Cross-over piping - Dwg. 719-J-662 -

|         |    |              |                          |
|---------|----|--------------|--------------------------|
| Item 7  | 12 | 1/2 Blankets | 19" x 64" x 3" thick     |
| Item 8  | 12 | 1/2 Blankets | 8" x 54" x 3" thick      |
| Item 9  | 12 | 1/2 Blankets | 3" x 54" x 3" thick      |
| Item 10 | 12 | 1/4 Rings    | 20.5" x 54.5" x 3" thick |
| Item 11 | 6  | Blankets     | 12.76 x 15" x 3" thick   |
| Item 12 | 6  | 1/2 Blankets | 4.5" x 76" x 3" thick    |

*+ OTHER  
CONNS  
?*

Blankets for Cross-under piping - Dwg. 719-J-667 -

|        |   |              |                             |
|--------|---|--------------|-----------------------------|
| Item 7 | 8 | 1/2 Blankets | 19" x 60" x 2-1/2" thick    |
| Item 8 | 8 | 1/2 Blankets | 2-1/2" x 52" x 2-1/2" thick |
| Item 9 | 8 | 1/2 Blankets | 8" x 52" x 2-1/2" thick     |

Main Steam Inlet Piping - Dwg. 721-J-210 -

|        |   |          |                       |
|--------|---|----------|-----------------------|
| Item 9 | 2 | Blankets | 32.5 Diam. x 3" thick |
|--------|---|----------|-----------------------|

(over)

Price As detailed herein.

Terms Net 30

This proposal is subject to the terms and conditions on the reverse side of this page.

ALS/mkm  
In duplicate

Respectfully submitted,  
EASTERN REFRACTORIES CO., INC.

By *Albert L. Sargent*  
Albert L. Sargent

# PROPOSAL

Robert A. Keasbey Company

|                    |                 |                                                   |
|--------------------|-----------------|---------------------------------------------------|
| Item 10            | 2 Blankets      | 12-1/2" x 112" x 3" thick                         |
| Item 11            | 2 Blankets      | 7" x 65" x 3" thick                               |
| Item 12            | 2 Blankets      | 17.5 Diam. x 3" thick                             |
| Item 13            | 2 Blankets      | 31.5 x 117" x 3" thick                            |
| Item 14            | 4 Blanket Rings | 34.24 Diam outer)<br>22.00 Diam inner) x 3" thick |
| Item 15            | 2 Blankets      | 12" x 148.88" x 3" thick                          |
| Items 16<br>and 17 | 8 1/4" Rings    | 13" x 31.5" x 3" thick                            |

Blankets will be built up with successive layers of ERCO-Mat to thicknesses specified and enclosed with AA Asbestos Cloth to meet Westinghouse Material Spec. 41511 Specification 600359 - Part 1.

Blankets will be quilted at 6" o.c. as specified and furnished with Cadmium plated ERCO Bergen Hooks and Washers to provide securements for proper installation.

Our estimate is based on the use of Hog rings for the final outside seams of all pads.

Our price for this schedule of prefabricated blankets will be the sum of \$6,580.00, shipped freight allowed to Indian Point Station, Buchanan, New York.

For the ERCO-Mat material only called for in Item 21 - Symbol C - Dwg. 721-J-210, we have figured on sixteen (16) Rolls @ 225 sq. ft. per roll or 3600 sq. ft. @ 0.64 per sq. ft., or a total of \$2,304.00 freight allowed to Indian Point Station, Buchanan, New York.

- - - -