Such procedures shall include, but are not necessarily limited to:

(1) Boilers and pipes insulated with asbestos-containing material shall be wetted and stripped before toppling of walls is begun. This procedure shall be followed, where practicable, as to all other asbestos-lined surfaces. Such asbestos waste shall be immediately bagged and disposed of in accordance with Sec. I(C).

(2) Demolition by toppling of walls is prohibited except within an enclosure approved by the Environmental Protection Agency as part of the permit granted for demolition of that structure.

(3) Before the demolition of any section of the structure, adequate wetting to suppress the dust shall be employed.

(4) Asbestos-containing debris shall not be dropped or thrown from any floor but shall be transported by dust-tight chutes or buckets. Asbestos-containing debris in chutes or buckets shall be sufficiently wetted to preclude dust dispersion at the point of discharge.

(5) All asbestos-containing debris shall be thoroughly wetted before loading into trucks, other vehicles or containers. During transport such waste shall be enclosed or covered so as to prevent dust dispersion. Asbestos-containing debris shall be disposed by burial at an approved site.