

STANDARD OIL COMPANY OF TEXAS
ENGINEERING DEPARTMENT - EL PASO, TEXAS

ADDENDUM NO. 1 TO SPECIFICATION
NO. EP-246-M
CONSTRUCTION OF THE EAST AND SOUTH
OFF-PLOT PIPEWAY STRUCTURES
January 13, 1971
Page 1

Specification No. EP-246-M has been revised as follows:

SECTION 1 - GENERAL REQUIREMENTS

1.1 SCOPE OF WORK

1.11 CONTRACTOR'S scope of work has been increased as follows:

a) This work includes but is not limited to:

7. Constructing and completing the pipeway stanchions in the following order: E-1, E-2, E-3, E-4, E-5, E-6, S-1, S-2, S-3, S-4 and S-5. This sequence of completion is necessary in order to permit the initiation of process pipe installation at the earliest possible date.
8. Excavating the entire length of the dirt bank under the South Pipeway approximately 9'-0" east so that the toe of the 1.5 to 1.0 slope is at E2177'-6" instead of E2168'-6". Reconstruct the berm at the top of the slope in accordance with Section B of drawing PD-27220.
9. Repairing the slope protection coating on the dirt banks under the East and South Pipeways.

SECTION 4 - CONSTRUCTION

The following paragraph has been added to Section 4:

4.6 SLOPE PROTECTION

- 4.61 Where the existing slope protection coating is destroyed during the construction work detailed in Specification No. EP-246-M, CONTRACTOR shall apply a new protective coating.
- 4.62 The protective coating shall be Chevron Asphalt Company's Texas MC-1 Penetrating Asphalt.
- 4.63 The coating shall be sprayed on at a rate of 3/4 gallon per square yard.
- 4.64 COMPANY will furnish the Texas MC-1 Penetrating Asphalt.

THIS PAGE ENDS ADDENDUM NO. 1